

I) RADIUS OF ELBOW SHALL BE AT LEAST 2xDIAMETER OF DISCHARGE STACK. THE ELBOW SHALL BE SECURELY HELD AND BOLTED TO THE BUILDING.

OFFSETS IN DISCHARGE STACK

2) THE CROSS-VENT PIPE SHOULD BE SLOPED UPWARDS FROM THE DISCHARGE STACK. IT SHALL BE OF THE SAME DIAMETER AS THE VENTILATING STACK.

ALL DIMENSIONS ARE IN mm.

OFFSET AND CROSS-VENT PIPE

